



PROJECT: TOWN OF DEER LAKE PAVING 2021

JOB# PW-01-2021



PROJECT: TOWN OF DEER LAKE PAVING 2021

JOB# PW-01-2021

Sealed tenders for the above project will be received at the Town Office up to 2:30 pm on Thursday, August 12, 2021. Street paving 2021 must be clearly written on outside on envelope.

Copies of the tender document can be obtained from the Town of Deer Lake office.

The Town of Deer Lake does not bind itself to accept the lowest or any tender. The Town may withdraw streets as funding allows.

Please contact David Thomas, Town Superintendent at (709) 635 2451 for more information.

- ASPHALT TO BE PLACED FOLLOWING MUNICIPAL MASTER SPECIFICATION.
- APPROVED MIX DESIGN SUBMITTED BEFORE COMMENCING WORK.
- MUST ADHERE TO ALL OCCUPATIONAL AND SAFETY REGULATIONS.
- TEN PERCENT BID BOND OR CERTIFIED CHEQUE REQUIRED.
- ASPHALT TO BE 50 MM THICK.
- LETTER OF GOOD STANDING FROM WORKERS COMPENSATION.
- CLASS A SHOULDERING MUST BE .75M WIDE AND TAPER TO INSIDE PROPERTY
- COR CERTIFIED.
- PAVING MUST BE COMPLETED WITHIN 20 DAYS OF THE AWARD OR TENDER WILL BE AWARDED TO NEXT LOWEST BIDDER.
- ALL DEBRIS FROM PROJECT MUST BE CLEANED UP AFTER JOB IS COMPLETED.



PROJECT: TOWN OF DEER LAKE PAVING 2021
JOB# PW-01-2021

<i>SECTION</i>	<i>DESCRIPTION</i>	<i>UNITS</i>	<i>QUANTITY</i>	<i>UNIT PRICE</i>	<i>TOTAL</i>
	<u>Mosses Lane</u>				
02233	Selected Granular Base & Subbase Class "A" Shouldering	M ³	15		
02547	Asphalt Tack Coat -Supply & Placement of Asphalt Tack Coat	M ²	1200		
02552	HOT Mix Asphalt – Concrete paving Surface Course	Tonne	170		
02574	Reshaping & patching Asphalt Paving - Cold Planing 1m pay width - Patching	M ² M ²	48		
02601	Manholes, Catch Basins, Ditch inlet And Valve Chambers - Manhole Grade Risers - Valve Box Grade Risers	Ea Ea			
				Mosses Lane Total	<hr/>
					<hr/>



PROJECT: TOWN OF DEER LAKE PAVING 2021
JOB# PW-01-2021

SECTION	DESCRIPTION	UNITS	QUANTITY	UNIT PRICE	TOTAL
	<u>Wellon Drive</u>				
02233	Selected Granular Base & Sub base Class "A" Shouldering	M ³	45		
02547	Asphalt Tack Coat -Supply & Placement of Asphalt Tack Coat	M ²	5400		
02552	H07 Mix Asphalt – Concrete paving Surface Course	Tonne	740		
02574	Reshaping & patching Asphalt Paving				
	- Cold Planing	M ²	285		
	-				
	- Patching	M ²			
02601	Manholes, Catch Basins, Ditch inlet And Valve Chambers				
	- Manhole Grade Risers	Ea	4		
	- Valve Box Grade Risers	Ea	4		
				Wellon Drive	
				Total	<hr/>



PROJECT: TOWN OF DEER LAKE PAVING 2020
JOB# PW-01-2020

<i>SECTION</i>	<i>DESCRIPTION</i>	<i>UNITS</i>	<i>QUANTITY</i>	<i>UNIT PRICE</i>	<i>TOTAL</i>
	<u>Langdons Avenue</u>				
02233	Selected Granular Base & Subbase Class "A" Shouldering	M ³	6		
02547	Asphalt Tack Coat -Supply & Placement of Asphalt Tack Coat	M ²	350		
02552	HOT Mix Asphalt – Concrete paving Surface Course	Tonne	65		
02574	Reshaping & patching Asphalt Paving - Cold Planing .75 pay width - Patching	M ² M ²	25		
02601	Manholes, Catch Basins, Ditch inlet And Valve Chambers - Manhole Grade Risers - Valve Box Grade Risers	Ea Ea			
				Langdons Avenue Total	



PROJECT: TOWN OF DEER LAKE PAVING 2021
JOB# PW-01-2021

<i>SECTION</i>	<i>DESCRIPTION</i>	<i>UNITS</i>	<i>QUANTITY</i>	<i>UNIT PRICE</i>	<i>TOTAL</i>
	<u>Cemetery Lane</u>				
02233	Selected Granular Base & Sub base Class "A" Shouldering	M ³	12		
02547	Asphalt Tack Coat -Supply & Placement of Asphalt Tack Coat	M ²			
02552	H07 Mix Asphalt – Concrete paving Surface Course	Tonne	170		
02574	Reshaping & patching Asphalt Paving				
	- Cold Planing	M ²			
	-				
	- Patching	M ²			
02601	Manholes, Catch Basins, Ditch inlet And Valve Chambers				
	- Manhole Grade Risers	Ea			
	- Valve Box Grade Risers	Ea			
				Cemetery Lane	
				Total	<hr/>
				HST Total	<hr/>
					<hr/>



PROJECT: TOWN OF DEER LAKE PAVING 2020
JOB# PW-01-2020

<i>SECTION</i>	<i>DESCRIPTION</i>	<i>UNITS</i>	<i>QUANTITY</i>	<i>UNIT PRICE</i>	<i>TOTAL</i>
	<u>Queen Street</u>				
02233	Selected Granular Base & Sub base Class "A" Shouldering	M ³	10		
02547	Asphalt Tack Coat -Supply & Placement of Asphalt Tack Coat	M ²	1200		
02552	H07 Mix Asphalt – Concrete paving Surface Course	Tonne	175		
02574	Reshaping & patching Asphalt Paving				
	- Cold Planing	M ²	125		
	-				
	- Patching	M ²			
02601	Manholes, Catch Basins, Ditch inlet And Valve Chambers				
	- Manhole Grade Risers	Ea	2		
	- Valve Box Grade Risers	Ea	1		
				Queen Street	
				Total	<hr/>
				HST Total	<hr/>
					<hr/>



PROJECT: TOWN OF DEER LAKE PAVING 2020
JOB# PW-01-2020

SECTION	DESCRIPTION	UNITS	QUANTITY	UNIT PRICE	TOTAL
	<u>Kennedy Street</u>				
02233	Selected Granular Base & Sub base Class "A" Shouldering	M ³	10		
02547	Asphalt Tack Coat -Supply & Placement of Asphalt Tack Coat	M ²	1200		
02552	H07 Mix Asphalt – Concrete paving Surface Course	Tonne	175		
02574	Reshaping & patching Asphalt Paving				
	- Cold Planing	M ²	110		
	-				
	- Patching	M ²			
02601	Manholes, Catch Basins, Ditch inlet And Valve Chambers				
	- Manhole Grade Risers	Ea	1		
	- Valve Box Grade Risers	Ea	2		
				Kennedy Street	
				Total	<hr/>
				HST Total	<hr/>
					<hr/>



PROJECT: TOWN OF DEER LAKE PAVING 2020
JOB# PW-01-2020

<i>SECTION</i>	<i>DESCRIPTION</i>	<i>UNITS</i>	<i>QUANTITY</i>	<i>UNIT PRICE</i>	<i>TOTAL</i>
	<u>Dr. T Milton Green Square</u>				
02233	Selected Granular Base & Sub base Class "A" Shouldering	M ³	1260		
02547	Asphalt Tack Coat -Supply & Placement of Asphalt Tack Coat	M ²			
02552	H07 Mix Asphalt – Concrete paving Surface Course	Tonne	190		
02574	Reshaping & patching Asphalt Paving				
	- Cold Planing	M ²	97		
	-				
	- Patching	M ²			
02601	Manholes, Catch Basins, Ditch inlet And Valve Chambers				
	- Manhole Grade Risers	Ea	3		
	- Valve Box Grade Risers	Ea			
				Dr. T Milton Green Square	
				Total	<hr/>
				HST Total	<hr/> <hr/>

