



PROJECT: TOWN OF DEER LAKE PAVING 2023

JOB# DL-01-2023



PROJECT: TOWN OF DEER LAKE PAVING 2023

JOB# DL-01-2023

Sealed tenders for the above project will be received at the Town Office up to 2:30 pm on Tuesday, July 25, 2023. Street paving 2023 must be clearly written on outside on envelope.

Copies of the tender document can be obtained from the Town of Deer Lake office.

The Town of Deer Lake does not bind itself to accept the lowest or any tender. The Town may withdraw streets as funding allows.

Please contact David Thomas, Director of Public Works and Development at (709) 635 2451 for more information.

- ASPHALT TO BE PLACED FOLLOWING MUNICIPAL MASTER SPECIFICATION.
- APPROVED MIX DESIGN SUBMITTED BEFORE COMMENCING WORK.
- MUST ADHERE TO ALL OCCUPATIONAL AND SAFETY REGULATIONS.
- TEN PERCENT BID BOND OR CERTIFIED CHEQUE REQUIRED.
- ASPHALT TO BE 50 MM THICK.
- LETTER OF GOOD STANDING FROM WORKERS COMPENSATION.
- CLASS A SHOULDERING MUST BE .75M WIDE AND TAPER TO INSIDE PROPERTY
- COR CERTIFIED.
- PAVING MUST BE COMPLETED WITHIN 20 DAYS OF THE AWARD OR TENDER WILL BE AWARDED TO NEXT LOWEST BIDDER.
- ALL DEBRIS FROM PROJECT MUST BE CLEANED UP AFTER JOB IS COMPLETED.
- Longitudinal joints not in wear path.
- No Recycled asphalt to be used.



PROJECT: TOWN OF DEER LAKE PAVING 2023
JOB# DL-01-2023

SECTION	DESCRIPTION	UNITS	QUANTITY	UNIT PRICE	TOTAL
	<u>Chapel Hill</u>				
02233	Selected Grandular Base & Subbase Class "A" Shouldering	M ³			
02547	Asphalt Tack Coat -Supply & Placement of Asphalt Tack Coat	M ²	3145		
02552	HOT Mix Asphalt – Concrete paving Surface Course	Tonne	600		
02574	Reshaping & patching Asphalt Paving				
	- Cold Planing 1m pay width	M ²	110		
	- Patching	M ²			
02601	Manholes, Catch Basins, Ditch inlet And Valve Chambers				
	- Manhole Grade Risers	Ea	8		
	- Valve Box Grade Risers	Ea	4		
				Chapel Hill Total	<hr/>
				HST Total	<hr/>



PROJECT: TOWN OF DEER LAKE PAVING 2023
JOB# DL-01-2023

SECTION	DESCRIPTION	UNITS	QUANTITY	UNIT PRICE	TOTAL
	<u>Wights Road</u>				
02233	Selected Grandular Base & Sub base Class "A" Shouldering	M ³			
02547	Asphalt Tack Coat -Supply & Placement of Asphalt Tack Coat	M ²	820		
02552	H07 Mix Asphalt – Concrete paving Surface Course	Tonne	120		
02574	Reshaping & patching Asphalt Paving				
	- Cold Planing	M ²	260		
	-				
	- Patching	M ²			
02601	Manholes, Catch Basins, Ditch inlet And Valve Chambers				
	- Manhole Grade Risers	Ea	1		
	- Valve Box Grade Risers	Ea	3		
				Wights Road	
				Total	<hr/>
				HST Total	

